

City of Kodiak
Underground Storage Tank Removal PN 21-12/5037
Addendum No. 1
April 7, 2021

The following change(s) and/or clarification(s) are made to the Plan and Specification Documents of Invitation to Bid for the Underground Storage Tank Removal PN 21-12/5037 dated 2021:

1. **This addendum answer Contractor questions.**

1. How much fuel is currently in each tank?

[There are approximately 10 gallons of fuel in each](#)

2. Will the owners QEP be doing stockpile characterization sampling or is that part of the contractors' responsibility?

[QEP will be doing stockpile characterization sampling](#)

3. Who is responsible for applying for an ADEC general construction dewatering permit?

[The Contractor will be responsible for applying for an ADEC General Construction Dewatering Permit](#)

4. Are the tank ballasts required to be removed or can they be abandoned in place?

[The tank ballasts are required to be removed](#)

5. Is there an alternative material we can use to hold down the contaminated cell liner instead of the specified 12" treated poles?

[The City will consider alternate materials to anchor the bottom liner against the dike](#)

6. If more than the specified contaminated soil/ water is encountered than the plans call for, is it going to be covered by change order to build storage cell bigger?

[Refer to the City of Kodiak Standard Construction Specification, Division 100, Article 11.03.D](#)

There are no changes to the Bid opening Time and Location.